FRENCH ROCKS DIVISION.

The 2nd April 1896.

In supersession of the Advertisement, dated 28th March 1896.

Tenders are hereby invited for re-constructing a new Anikat across the river Hemavati at Kalhalli Krishnarajpete Taluk, Mysore District.

2. The plans, estimates, schedule of rates, and conditions may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor, and forwarded in sealed covers to the Executive Engineer before the 17th April 1896. The work should be completed by the end of June 1897.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 1,000 as earnest money.

6. Within eight days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate, in quantities of items of work required, is given below. These quantities are not guaranteed.

10. Suitable stone for the construction of the anikat will be supplied to the contractor by the Government at the site of the works. The tenders now called for being only for the manufacture and supply of the specified mortar and for building with required stone dressing.

Anikat 1,000 feet long, 8 feet wide with front batter of 1 in 4.

Items of Work.	*Per.*	*Quantity.*
Blasting rock	C.yds.	8
Benching rock	S.ft.	9,891
Earthwork excavation, ordinary soil	C.yds.	180
Stone masonry in surki	C.ft.	71,004
Roughly chiselled stone in surki	Do	12,767
Chisel dressing coping	S.ft.	6,774
Pointing with portland cement	Sqr.	266·79
Baling	L. S.	Rs.
Inspection lodge	Do	Do

THOS. INMAN, *Executive Engineer.*

BANGALORE CITY MUNICIPALITY.

Notice, dated 15th April 1896.

Under Section 21 of the Municipal Regulations the following additional proposition will be laid before the Board for discussion at the ordinary meeting to be held on Tuesday, 28th April 1896.

1. Government Proceedings No 11475-6—L. F. 11-93, dated 10th April 1896, *in-re* the appointment of N. Raghunatha Rao retired P. W. Sub-Overseer as P. W. Overseer of the Bangalore City Municipality.

Notice, dated 17th April 1896.

Under Section 21 of the Municipal Regulations the following additional propositions will be laid before the Board for discussion at the ordinary meeting to be held on Tuesday the 28th April 1896.

2. Government Proceedings No. 11670—L. F. 43-92, dated 15th April 1896, on the subject of the contribution payable by the Civil and Military Station Municipality on account of patients from the said station resorting to the City Maternity.

3. Re-appropriation statement of funds out of the sanctioned Budget on Public Works for 1895-96.